

LEGEND	
CODE	DESCRIPTION
P1	100mm THK GYPSUM BOARD PARTITION FROM STRUCTURAL FLOOR SLAB TO STRUCTURAL CEILING SLAB, W/ 52mm METAL STUD, TWO LAYERS OF 12mm GYPSUM BOARD ON BOTH SIDES, W/ 80kg ROCK WOOL INSULATION THROUGHOUT.
P2	DOUBLE GLAZED PARTITION w/ 12mm + 10mm THK TEMPERED GLASS FROM STRUCTURAL FLOOR SLAB TO 2800mmH LEVEL W/ CHAMPAIGN GOLD COLOR METAL FRAME (REFER TO SHOP DRAWING) (BRAND : BY JEB OR EQUIVALENT)
P3	100mm THK GYPSUM BOARD PARTITION FROM 2800mmH LEVEL TO STRUCTURAL CEILING SLAB, W/ 52mm METAL STUD, TWO LAYERS OF 12mm GYPSUM BOARD ON BOTH SIDES, W/ 60kg ROCK WOOL INSULATION THROUGHOUT.
P4	75mm THK GYPSUM BOARD PARTITION FROM STRUCTURAL FLOOR SLAB TO STRUCTURAL CEILING SLAB, W/ 52mm METAL STUD, ONE LAYERS OF 12mm GYPSUM BOARD ON BOTH SIDES, W/ 60kg ROCK WOOL INSULATION THROUGHOUT.
P5	75mm THK GYPSUM BOARD PARTITION FROM 2800mmH LEVEL TO STRUCTURAL CEILING SLAB, W/ 52mm METAL STUD, ONE LAYERS OF 12mm GYPSUM BOARD ON BOTH SIDES, W/ 60kg ROCK WOOL INSULATION THROUGHOUT.
PCW	105mm THK POWER COLUMN (CHAMPAIGN GOLD COLOR METAL FINISHES, BRAND : JEB OR EQUIVALENT)
FUR	TYPICAL FURRING WALL W/ PLYWOOD BACKING FOR MOUNTING TV OR OTHERS PLEASE ALLOW ACCESS DOOR IF THERE ARE PIPE INSIDE THE FURRING

REMARKS

- PLEASE REFER TO SECTION 03 PARTITION FOR MORE DETAILED SPECIFICATIONS.
- SITE INSPECTION TO EXISTING AT OFFICE TO BE ARRANGED BY PROJECT MANAGER.
- CONTRACTOR TO ADD PLYWOOD FURRING AT THE AREA WHERE AV EQUIPMENTS OR JOINERY TO BE MOUNTED.
- PLEASE ALLOW ALL STRUCTURAL COLUMN TO BE FURRED WITH GYPSUM BOARD.

